

## Contactor, 3p+1N/0, 11kW/400V/AC3

Part no. DILM25-10(48V50HZ)
Article no. 277120
Catalog No. XTCE025C10Y



## Design verification as per IEC/EN 61439

Design verification as per 120/214 01-103			
Technical data for design verification			
Rated operational current for specified heat dissipation	In	Α	25
Heat dissipation per pole, current-dependent	P <sub>vid</sub>	W	1.4
Equipment heat dissipation, current-dependent	P <sub>vid</sub>	W	4.2
Static heat dissipation, non-current-dependent	$P_{vs}$	W	2.1
Heat dissipation capacity	P <sub>diss</sub>	W	0
IEC/EN 61439 design verification			
10.2 Strength of materials and parts			
10.2.2 Corrosion resistance			Meets the product standard's requirements.
10.2.3.1 Verification of thermal stability of enclosures			Meets the product standard's requirements.
10.2.3.2 Verification of resistance of insulating materials to normal heat			Meets the product standard's requirements.
10.2.3.3 Verification of resistance of insulating materials to abnormal heat and fire due to internal electric effects			Meets the product standard's requirements.
10.2.4 Resistance to ultra-violet (UV) radiation			Meets the product standard's requirements.
10.2.5 Lifting			Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 Mechanical impact			Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 Inscriptions			Meets the product standard's requirements.
10.3 Degree of protection of ASSEMBLIES			Does not apply, since the entire switchgear needs to be evaluated.
10.4 Clearances and creepage distances			Meets the product standard's requirements.
10.5 Protection against electric shock			Does not apply, since the entire switchgear needs to be evaluated.
10.6 Incorporation of switching devices and components			Does not apply, since the entire switchgear needs to be evaluated.
10.7 Internal electrical circuits and connections			Is the panel builder's responsibility.
10.8 Connections for external conductors			Is the panel builder's responsibility.
10.9 Insulation properties			
10.9.2 Power-frequency electric strength			Is the panel builder's responsibility.
10.9.3 Impulse withstand voltage			Is the panel builder's responsibility.
10.9.4 Testing of enclosures made of insulating material			Is the panel builder's responsibility.
10.10 Temperature rise			The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 Short-circuit rating			Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 Electromagnetic compatibility			Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.13 Mechanical function			The device meets the requirements, provided the information in the instruction leaflet (IL) is observed.

## **Technical data ETIM 5.0**

Low-voltage industrial components (EG000017) / Magnet contactor, AC-switching (E	C000066)			
Electric engineering, automation, process control engineering / Low-voltage switch technology / Contactor (LV) / Power contactor, AC switching (ecl@ss8-27-37-10-03 [AAB718011])				
Rated control supply voltage Us at AC 50HZ	V	48 - 48		
Rated control supply voltage Us at AC 60HZ	V	0 - 0		
Rated control supply voltage Us at DC	V	0 - 0		
Voltage type for actuating		AC		
Rated operation current le at AC-1, 400 V	А	45		
Rated operation current le at AC-3, 400 V	Α	25		
Rated operation power at AC-3, 400 V	kW	11		
Rated operation current le at AC-4, 400 V	А	13		
Rated operation power le at AC-4, 400 V	kW	6		

Modular version	No
Number of auxiliary contacts as normally open contact	1
Number of auxiliary contacts as normally closed contact	0
Connection type main current circuit	Screw connection
Number of normally closed contacts as main contact	0
Number of main contacts as normally open contact	3

## **Dimensions**



